

East Fork Lewis River Reconnection Project
DRAFT PRICE SCHEDULE

ITEM NO.	SPEC	ITEM DESCRIPTION	EST. QNTY	UNIT	UNIT PRICE	TOTAL EST. PRICE
1	1-09	Mobilization	1	LS		
2	8-34	Field Office Building	1	LS		
3	1-05	Construction Surveying	1	LS		
4	1-10	Traffic Control	1	LS		
5	8-01	TESC Plan and Implementation	1	LS		
6	2-01	Clearing And Grubbing	1	LS		
7	8-19	Temporary Access Bridge, EF Lewis River	1	LS		
8	8-19	Temporary Access Bridge, East Floodplain	1	LS		
9	2-02	Demo - 24 In Dia CMP Culverts	3	EA		
10	2-02	Demo - Danger Park Asphalt Road	1	LS		
11	2-02	Demo - Daybreak Asphalt Trail	1	LS		
12	2-02	Demo - Daybreak Concrete Pad	1	LS		
13	2-02	Remove/Salvage - Daybreak Gravel Trail	1	LS		
14	2-02	Demo - Chain Link Fence	409	LF		
15	8-31	Work Area Isolation and Dewatering	1	LS		
16	2-03	Subgrade Excavation – Dyer Creek Seasonal Fords	70	CY		
17	2-03	Subgrade Excavation – County Yard Maintenance Pad (Gravel)	7,070	CY		
18	2-03	Subgrade Excavation – Daybreak Park Trails	510	CY		
19	2-05	Excavation - Channels	78,770	CY		
20	2-05	Excavation - Floodplain	247,030	CY		
21	2-05	Excavation - Daybreak Floodplain, Haul to Local Spoils Area	41,660	CY		
22	2-05	Excavation – Salvage and Place Riprap	3,380	CY		
23	2-05	Excavation – Salvage and Place Topsoil Amendment	8,400	CY		
24	2-05	Excavation – Salvage and Place Crushed Rock	5,110	CY		

ITEM NO.	SPEC	ITEM DESCRIPTION	EST. QNTY	UNIT	UNIT PRICE	TOTAL EST. PRICE
25	8-26	LW Haul – Logs with Roots	1,006	EA		
26	8-26	LW Haul – Logs without Roots	569	EA		
27	8-26	LW Haul – Pile Logs	1,169	EA		
28	8-26	LW Installation – (A) Small Bank Buried Structures	54	EA		
29	8-26	LW Installation – (B) Large Bank Buried Structures	27	EA		
30	8-26	LW Installation – (C) Small Whole Tree Structures	49	EA		
31	8-26	LW Installation – (D) Large Whole Tree Structures	10	EA		
32	8-26	LW Installation – (E) Margin Habitat Structures	13	EA		
33	8-26	LW Installation – (F) Apex Structures	3	EA		
34	8-26	LW Installation – (G) Minor Inlet Structures	4	EA		
35	8-26	LW Installation – (H) Major Inlet Structures	4	EA		
36	8-26	LW Installation – (I) Alcove Pool Structures	57	EA		
37	8-26	LW Installation – (J) Pile Fence Structures	13	EA		
38	8-26	LW Installation – (K) Type 1 Floodplain Roughness Structures	72	EA		
39	8-26	LW Installation – (L) Type 2 Floodplain Roughness Structures	123	EA		
40	8-15	Quarry Spalls – Dyer Creek Seasonal Fords	70	CY		
41	6-20	Reinforced Concrete Box Culvert, 6 X 10 FT	1	LS		
42	4-04	Crushed Surfacing Base Course – Daybreak Asphalt Trail	490	TN		
43	5-04	HMA CL. 3/8 In. PG - Daybreak Trail	330	TN		
44	4-04	Gravel Trail Base Course - 5/8 In. Minus	90	CY		
45	4-04	Gravel Trail Surfacing Course - 3/8 In. Minus	44	CY		
46	8-12	Chain Link Fence, Type 3	873	LF		
47	8-12	Chain Link Rolling Gate, 24 Ft Wide	2	EA		
48	8-02	Hydroseed - Wetland and Willow Scrub	63.2	AC		
49	8-02	Hydroseed - Riparian	65.6	AC		
50	8-02	Willow Trenches - 4 Foot Live Cuttings	3,210	LF		
51	8-02	Willow Trenches - 5+ Foot Live Cuttings	4,560	LF		
SUBTOTAL (Bid Items 1 Thru 51)						
WA STATE SALES TAX (7.8%)						
BASE TOTAL (Bid Items 1 Thru 51 + Tax)						

Bid Alternates and Contingencies

ITEM NO.	SPEC	ITEM DESCRIPTION	EST. QNTY	UNIT	UNIT PRICE	TOTAL EST. PRICE
A-1	2-03	Bid Alternate - Reduced Subgrade Excavation for Asphalt County Yard Maintenance Pad	1,115	CY		
A-2	4-04	Bid Alternate - Crushed Surfacing Base Course - County Yard Asphalt Pad	2,360	TN		
A-3	5-04	Bid Alternate - HMA CL. 3/8 In. PG - County Yard Pad	980	TN		
A-4	2-05	Bid Alternate - Excavation - Daybreak, Haul to Core Pits	7,620	CY		
A-5	8-26	Bid Alternate - LW Procurement - Logs with Roots	TBD	EA		
A-6	8-26	Bid Alternate - LW Procurement - Logs without Roots	TBD	EA		
A-7	8-26	Bid Alternate - LW Procurement - Pile Logs	TBD	EA		
C-1	2-05	Contingency – Additional Topsoil Amendment	100	CY		
C-2	2-05	Contingency – Supplemental Placement of Coarse Substrate	100	CY		
C-3	General	Delay Damages - May 9	24	DAY		